# BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Project Division
B.B.M.P. Bangalore - 92

## Modified SCHEDULE-B

Issued to :

Original / Duplicate

**Name of Work:Extension of Reva College Road upto CISF compound (BBMP limits)**

| Sl. No. | Approved Quantity | Description | Unit | ModifiedQuantity | Sanctioned Rates | Rates Quoted by the Contractor | |
|---|---|---|---|---|---|---|---|
| | | | | | | In Figures | In Words |
| 1 | 26.88 | KSRRB M200-12.1. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry,cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications.111) KSRRB M200-12.3. –do– C. Prestressed / Reinforced cement concrete grade M-20 & above.MORTH specification No.202 with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 23.15 | 954.72 | 954.72 | Rupees Nine Hundred Fifty Four And Paise Seventy Two Only |
| 2 | 728.40 | KSRRB M200-14.1. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. KSRRB M200-14.2. –do– Dismantling brick/Tile work B. In cement mortar. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 619.28 | 226.80 | 226.80 | Rupees Two Hundred Twenty Six And Paise Eighty Only |
| 3 | 408.00 | KSRRB M200-15.1. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specifications. KSRRB M200- 15.2. –do– B. Rubble stone masonry in cement mortar. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 333.00 | 226.80 | 226.80 | Rupees Two Hundred Twenty Six And Paise Eighty Only |

20/2/17

Executive Engineer,

| Sl. No. | Approved Quantity | Description | Unit | ModifiedQuantity | Sanctioned Rates | Rates Quoted by the Contractor | |
|---|---|---|---|---|---|---|---|
| | | | | | | In Figures | In Words |
| 10 | 1939.20 | KSRRB M300-55. Construction of sub-grade and earthen shoulders with approved material Gravel/Murrum with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table No. 300-2 complete as per specifications (including cost of earth, watering charges & compaction by vibratory roller) MORTH Specification No. 305 with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 698.54 | 252.72 | 252.72 | Rupees Two Hundred Fifty Two And Paise Seventy Two Only |
| 11 | 484.80 | KSRRB M400-6.1. Construction of granular sub-base by providing close graded material, mixing in a mechanical mix plant at OMC, carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the desired density, complete as per specifications. For Grading II Material. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 523.91 | 1298.16 | 1298.16 | Rupees One Thousand Two Hundred Ninety Eight And Paise Sixteen Only |
| 12 | 484.80 | KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 523.91 | 1438.56 | 1500.00 | Rupees One Thousand Five Hundred Only |
| 13 | 3232.00 | KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Sqm | 3492.72 | 35.21 | 35.21 | Rupees Thirty Five And Paise Twenty One Only |
| 14 | 6464.00 | KSRRB M500-7. Providing and applying tack coat on the prepared black topped surfaces at 2.5 Kg per 10 Sqm, heating bitumen in boiler fitted with spray set ( excluding cleaning of road surface ) including cost of all materials, labour, HOM of machineries complete as per specifications. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Sqm | 6985.44 | 18.74 | 18.74 | Rupees Eighteen And Paise Seventy Four Only |

20/2/17

Executive Engineer,

| Sl. No. | Approved Quantity | Description | Unit | ModifiedQuantity | Sanctioned Rates | Rates Quoted by the Contractor | |
|---|---|---|---|---|---|---|---|
| | | | | | | In Figures | In Words |
| 4 | 21.60 | KSRRB M200-15.1. Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T&P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts complete asper specifications.– v) KSRRB M200-17.1.Steel work in all types of Sections uptoa Height of 5 m above plinth level excluding Cutting of Rivet. – A.Including dismembering." with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 20.10 | 1123.20 | 1150.00 | Rupees One Thousand One Hundred Fifty Only |
| 5 | 171.00 | Dismantling cement concrete flooring or plain cement concrete work including removing and conveying the debris to distance upto 200m (within average thickness of 15 cms). with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Sqm | 166.50 | 50.76 | 50.76 | Rupees Fifty And Paise Seventy Six Only |
| 6 | 112.00 | KSRRB M200-23.1. Dismantling of flexible pavements and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. II. By Mechanical Means: A. Bituminous courses. MORTH Specification No. 202 with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 138.60 | 470.88 | 470.88 | Rupees Four Hundred Seventy And Paise Eighty Eight Only |
| 7 | 90.00 | Hire Charges of JCB, with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Day | 90.00 | 6720.00 | 6720.00 | Rupees Six Thousand Seven Hundred Twenty Only |
| 8 | 150.00 | Hire Charges of Tipper, with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Day | 150.00 | 1920.00 | 1920.00 | Rupees One Thousand Nine Hundred Twenty Only |
| 9 | 1697.28 | KSRRB M300-11. Excavation for road way in soil by mechanical means including cutting and pushing the earth to site of embankment upto a including trimming bottom and side slopes in accordance with requirements of lines, grades and cross sectins complete as per specifications . with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 1047.82 | 193.75 | 193.75 | Rupees One Hundred Ninety Three And Paise Seventy Five Only |

20/2/17

Executive Engineer,

| Sl. No. | Approved Quantity | Description | Unit | ModifiedQuantity | Sanctioned Rates | Rates Quoted by the Contractor | |
|---|---|---|---|---|---|---|---|
| | | | | | | In Figures | In Words |
| 15 | 161.60 | KSRRB 500-16. Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base or binding coarse including loading of aggregates with F.e loader hotmixing of stone aggregates and bitumen in hotmix plant 40 Tonnes capacity, transporting the mixed material in tipper To paver and laying with paver finisher To the required grade rolling by power roller To aachieve the desired density, 50x75mm compacted thickness with 3.3% bitumen but excluding cost of primer or tack coat with lead upTo 1km including cost of all materials, labour as per specifications With 60/70 grade bitumen with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 174.64 | 7482.24 | 7482.24 | Rupees Seven Thousand Four Hundred Eighty Two And Paise Twenty Four Only |
| 16 | 129.28 | Providing and laying bituminous concrete 40mm thick with 100-120 TPH batch type hot mix plant producing as average output of 75 Tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 To 5.6% 5.00 of mix and filler, transporting the hot mix To work site, laying with a hydrostatic paver finisher with sensor control To the required grade, level and alignment, rolling with smooth wheeled, vibraTory and tandem rollers To achieve the desired compaction as per MORTH specification clause No. 500.9 complete in all respects, with 40 mm compacted thickness (Grading II) with 6% Bitumen 60/70 grade using 40-60 HMP using mechanical paver with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 139.71 | 11552.49 | 12000.00 | Rupees Twelve Thousand Only |
| 17 | 120.00 | KSRRB M800-13. Providing and Laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.MORTH Specification No. 803 Road Marking with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Sqm | 148.50 | 475.20 | 475.20 | Rupees Four Hundred Seventy Five And Paise Twenty Only |
| 18 | 2795.34 | Cost of Plastic@ 8% of bitumen qty For Bituminous concrete with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Nos | 3137.40 | 27.00 | 27.00 | Rupees Twenty Seven Only |

20/2/17

Executive Engineer,

| Sl. No. | Approved Quantity | Description | Unit | ModifiedQuantity | Sanctioned Rates | Rates Quoted by the Contractor | |
|---|---|---|---|---|---|---|---|
| | | | | | | In Figures | In Words |
| 19 | 351.00 | KSRRB 300 - 1 : Earthwork excavation by manulal means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / chapter 3 with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 428.22 | 171.29 | 171.29 | Rupees One Hundred Seventy One And Paise Twenty Nine Only |
| 20 | 3.00 | KSRB 4-1.2: Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, machine mixd, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, cost of all materials, labour, HOM of machinery, curing complete as per specifications. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 5.46 | 6303.64 | 6400.00 | Rupees Six Thousand Four Hundred Only |
| 21 | 16.20 | KSRB 5.3-3: Providing and constructing granite/trap/basalt size stone masonary in basement with cement mortat 1:6, edges of stones chistle dressed in courses not less than 15cm high, bond stones at 2m apart in each course including cost of mterials, labour, scaffolding, curing complete as per specifications. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 19.66 | 4542.48 | 4650.00 | Rupees Four Thousand Six Hundred Fifty Only |
| 22 | 2.03 | KSRB 4-1.7 Providing and laying in position plain cement concrete of nominal mix M15 for coping concrete using cement @ 220kgs, with 20mm and down size graded metal coarse aggregate @ 0.84 cum and fine aggregates @ 0.56 cum, machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specifications No. KBS 4.1, 4.2 as directed by the Engineer and as per detailed tender specifications.etc., complete. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Cum | 2.46 | 5287.68 | 5300.00 | Rupees Five Thousand Three Hundred Only |

20/2/17

Executive Engineer,

| Sl. No. | Approved Quantity | Description | Unit | ModifiedQuantity | Sanctioned Rates | Rates Quoted by the Contractor | |
|---|---|---|---|---|---|---|---|
| | | | | | | In Figures | In Words |
| 23 | 900.00 | Providing granite slabs of selected qualitynroughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete 7.5cm thick with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Sqm | 1053.00 | 639.36 | 700.00 | Rupees Seven Hundred Only |
| 24 | 600.00 | Pre-cast Drain Cover Slab {size 1.5x0.6x0.1}:- Providing and laying pre-cast drain cover slab of 100mm thickness in CM1:3 including cost of all materials,labour,curing, transportation, loading, unloading etc.,as per doiirections of the Enineer-in-charge with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Sqm | 631.80 | 1659.00 | 1700.00 | Rupees One Thousand Seven Hundred Only |
| 25 | 45.00 | Providing & laying precast drain cover slab of 250 mm thickness in CM 1:3 including cost of all materials, labour, curing, transportation, loading, unloading etc, complete as per the directions of the Engineer In Charge.( 1.50 x 0.45 x 0.25) | Sqm | 54.60 | 4993.00 | 5000.00 | Rupees Five Thousand Only |
| 26 | 1,333.33 | Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | No | 1560.00 | 304.56 | 310.00 | Rupees Three Hundred Ten Only |
| 27 | 240.00 | KSRRB M800-6. Painting two coats on New Concrete Surface:-Painting two coats after filling the surface with synthetic enamel paint in all shades on new plastered concrete surfaces complete as per specifications. On Kerb Stone with all lead and lifts as per Specifications and the directions of the Engineer In-charge of the work. | Sqm | 280.80 | 61.56 | 66.00 | Rupees Sixty Six Only |
| 28 | Extra Item | KSRB 5-11 : Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 5.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing complete as per specifications. KBS No.5.4(P-24/5.26.2) SR 2016-17 | Sqm | 280.80 | --- | 980.65 | Rupees Nine Hundred Eighty And Paise Sixty Five Only |

I am prepared to execute work at the rates written by me in Schedule'B'

20/2/17

Executive Engineer,
Project Division, Yelahanka Zone